

## MEMORANDUM

May 22, 2018

**File:** A/37/18  
**Address:** 41 Elgin Street, Thornhill  
**Owner:** Mohammad Reza Eskandari  
**Applicant:** KLM Planning Partners Inc. (Roy Mason)  
**Hearing Date:** Wednesday May 30, 2018

As an update to the previous comments provided for the May 9, 2018 Committee of Adjustment Hearing (Attachment 1), Planning staff provides the following comments on behalf of the West Team:

The applicant is requesting relief from the following requirements of By-law 2237, as amended By Infill By-law 101-90 to permit:

**a) Section 6.1:**

a minimum west side yard setback of 1.68 m (5.52 ft.); whereas, the by-law permits a minimum side yard setback of 1.8 metres (5.90 ft.) on each side;

**b) Infill By-law 101-90; Section 1.2(iv):**

a maximum building depth of 21.47 metres (70.44 ft.); whereas, the by-law permits a maximum building depth of 16.8 metres (55.12 ft.);

**c) Infill By-law 101-90; Section 1.2 (i):**

a maximum building height of 10.19 m (33.43 ft.); whereas, the by-law permits a maximum building height of 9.8 m (32.15 ft.);

The variances relate to a proposed two storey dwelling.

The proponent has modified their proposal to address comments they received from the Committee of Adjustment at its meeting on May 9, 2018.

Planning Staff have reviewed the revised application with respect to Section 45(1) of The Planning Act, R.S.O. 1990, c. P.13, as amended, and have no concerns, subject to the comment outlined below:


1. That the conditions in Appendix 'A' to the previous Staff report dated May 1, 2018 shall be attached to any approval of this revised application.

PREPARED BY:



Rick Cefaratti, Planner II, West District

REVIEWED BY:



David Miller, MCIP, RPP, West District Manager

Att.

File Path: Amanda\File\18 228380\Documents\District Team Short Report Memo

### **Site Plan Approval Required**

The property is subject to Site Plan Control. Staff are currently reviewing an associated Site Plan application for the proposed dwelling under file SC 17 134485.

### **Applicant's Stated Reason(s) for Not Complying with Zoning**

According to the applicant, the reason for not complying with zoning is due to "design restriction and to be in line with the aesthetic and scale of other houses in the area".

### **Zoning Preliminary Review Undertaken**

Prior to submitting the current variance application, the applicant completed a Zoning Preliminary Review (ZPR) to confirm the variances required for a proposed two storey dwelling on the subject property. The plans submitted with the variance application were revised after the ZPR was completed. It is the owner's responsibility to ensure that the application has accurately identified all the variances to the Zoning By-law required for the proposed development. If the variances in the application contains errors, or if the need for additional variances are identified during the Site Plan application review process, further variance application(s) may be required to address the outstanding matters and there will be a delay in application processing.

### **Official Plan**

The subject property is designated "Residential – Low Rise" under the 2014 Markham Official Plan. This designation provides for single detached dwellings. The Official Plan specifies that new infill development respects the existing pattern and character of adjacent development and that new buildings shall have a complementary relationship with existing buildings, while accommodating a diversity of building styles, materials and colours. In addition, front and rear yard setbacks for new buildings shall be consistent with the front and rear yards that exist on the same side of the street.

### **Zoning**

The subject property is zoned Single Family Residential (R2) by By-law 2237, as amended.

### **Residential Infill By-law**

The property is also subject to Residential Infill Zoning By-law 101-90. The intent of the by-law amendment is to ensure that the residential redevelopment reflects the neighbourhood character. The infill By-law specifies zoning standards for building depth, garage projection, garage width, floor area ratio, height, front yard setback, and number of storeys.

### **Comments**

The Planning Act states that four tests must be met in order for a variance to be granted by the Committee of Adjustment:

- a) The variance must be minor in nature;
- b) The variance must be desirable, in the opinion of the Committee of Adjustment, for the appropriate development or use of land, building or structure;
- c) The general intent and purpose of the Zoning By-law must be maintained;

- d) The general intent and purpose of the Official Plan must be maintained.

### **Nature of the Variances**

#### **Increased Building Height Variance**

The applicant is requesting to permit a maximum building height of 10.6 m (34.77 ft.), whereas a maximum height of 9.8 m (32.15 ft.) is permitted. This represents an increased height of 0.8 m (2.62 ft.) or 8.16 percent. The proposed maximum building height is generally consistent with other infill homes in the surrounding community. Staff does not anticipate any adverse impacts and, therefore, have no objections to the requested building height variance.

#### **Increased Building Depth Variance**

Building depth is defined as the shortest distance between two lines, both parallel to the front lot line, one passing through the point of the dwelling which is nearest and the other through the point of the dwelling which is farthest from the front lot line. The applicant is requesting a building depth of 21.47 metres (70.44 ft.) for the proposed dwelling, whereas a maximum building depth of 16.80 m (55.10 ft.) is permitted. This represents an increase in building depth of 4.67 m (15.32 ft.) or approximately 27.8 percent. The requested building depth relates to a covered front porch as well as a breakfast nook and second floor master bedroom at the rear of the proposed dwelling. It is noted that the rear building projection above the covered lower porch/uncovered deck does not extend the full width of the building. Without these projections, the building length is approximately 19.0 m (62.33 ft.). Staff has no objections to the requested building depth variance.

Staff further note that, based on the plans submitted with the variance application, the proposed stairs and landings at the rear of the dwelling could create an undesirable overlook condition due to the walkout condition at the rear. The applicant should consider providing visual mitigation of these stairs by maintaining some of the existing vegetation in the rear yard as well as additional planting and/or privacy screening. Staff will work with the applicant to address this matter through the Site Plan approval process.

#### **Reduced Side Yard Setback**

The applicant is requesting a minimum side yard setback of 1.52 m (5.0 ft.) for the west side of the proposed dwelling, whereas the By-law requires a minimum side yard setback of 1.8 m (6.0 ft.) for both sides. It is noted that the proposed west side yard setback is identical to the west side yard setback for the existing dwelling on the property. Staff does not anticipate any adverse impacts and, therefore, have no objections to the requested building variance.

### **PUBLIC INPUT SUMMARY**

No written submissions were received as of May 1, 2018. Additional information may be received after the writing of this report. The Secretary-Treasurer will provide information on this at the meeting.

### **CONCLUSION**

Staff are of the opinion that the requested variances satisfy the four tests of the Planning Act. It is recommended that the Committee consider public input in reaching a decision. The onus is ultimately on the applicant to demonstrate why they should be granted relief from the requirements of the Zoning By-law, and how they satisfy the tests of the Planning Act for the granting of minor variances.


Please see Appendix "A" for conditions to be attached to any approval of this application.

PREPARED BY:



Rick Gifaratti, MCIP, RPP, Planner II, West District

REVIEWED BY:



David Miller, MCIP, RPP, Manager, West District

File Path: Amanda\File\ 18 228380 \Documents\District Team Comments Memo

**APPENDIX "A"**

**CONDITIONS TO BE ATTACHED TO ANY APPROVAL OF FILE A/37/18**


1. The variances apply only to the proposed development as long as it remains;
2. That the variances apply only to the subject development, in substantial conformity with the plan(s) attached as 'Appendix A' to this Staff Report and dated April 4, 2018, and that the Secretary-Treasurer receive written confirmation from the Director of Planning and Urban Design or designate that this condition has been fulfilled to his or her satisfaction;
3. Submission of a Tree Assessment and Preservation Plan, prepared by a qualified arborist in accordance with the City's Streetscape Manual (2009), as amended, to be reviewed and approved by the City, and that the Secretary-Treasurer receive written confirmation from the Director of Planning and Urban Design or designate that this condition has been fulfilled to his/her satisfaction of, and that any detailed Siting, Lot Grading and Servicing Plan required as a condition of approval reflects the Tree Assessment and Preservation Plan.
4. That prior to the commencement of construction or demolition, tree protection be erected around all trees on site, including street trees, in accordance with the City's Streetscape Manual (2009) as amended, and inspected by City Staff to the satisfaction of the Director of Planning and Urban Design or their designate.
5. That tree replacements be provided and/or tree replacement fees be paid to the City if required in accordance with the Tree Assessment and Preservation Plan, and that the Secretary-Treasurer receive written confirmation that this condition has been fulfilled to the satisfaction of the Director of Planning and Urban Design or designate;
6. That the applicant obtains Site Plan approval.

CONDITIONS PREPARED BY:



Rick Cefaratti, MCIP, RPP, Planner II, West District





ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY UNLESS APPROVED BY THE CITY AND MUST NOT BE USED FOR ANY CONSTRUCTION OR CORE EVIDENCE OF BELIEF OR FOR CONTRACTS OR BUSINESS MADE WITHOUT ALL NECESSARY SPECIFICATIONS AS WELL AS PERFORMANCES INCLUDING STRUCTURAL AND MECHANICAL PRIOR TO COMMENCEMENT OF WORK AND BEFORE ANY DISCHARGE TO MEMAR.

DESIGN DRAWINGS & SPECIFICATIONS ARE THE PROPERTY OF MEMAR ARCHITECTS INC. AND MUST NOT BE USED FOR ANY OTHER PROJECT AND/OR BY ANY OTHER PERSON WITHOUT ORIGINAL CLIENT'S WRITTEN PERMISSION.

DATE:	ISSUED FOR:
FEB 29-2018	FOR ZONING REVIEW APPLICATION
MAR 26-2018	FOR COA APPLICATION

DRAWING TITLE:
-1. SITE PLAN-2
PROJECT TITLE/ADDRESS:
41 ELGIN ST, MARKHAM

DRAWN BY:
D.N.
CHECKED BY:
S.T.

SCALE:
1:500, 1:200
LAST MODIFIED ON:
Wednesday, April 4, 2018



"Memor Architects Inc."  
 2323 Yonge St, Unit 503  
 Toronto, ON, M4P 2C9  
 T: 416-575-4448



A.04


+10.60  
5 TOP OF ROOF - 182.28

+8.05  
4 FIN SECOND FL CEILING - 179.74

+5.00  
3 FN SECOND FL - 176.69

+0.97  
2 FN GROUND FL - 172.65

-2.92  
0 FN BSMT FL - 168.71



+10.60  
5 TOP OF ROOF - 182.28

+8.05  
4 FIN SECOND FL CEILING - 179.74

+5.00  
3 FN SECOND FL - 176.69

+0.97  
2 FN GROUND FL - 172.65

-2.92  
0 FN BSMT FL - 168.71

ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY UNLESS APPROVED BY THE CITY AND MUST NOT BE USED FOR ANY CONSTRUCTION WITHOUT THE SIGNATURE OF BUILDING PERMIT CONTRACTOR/ENGINEER. MUST VERIFY ALL DIMENSIONS/STRUCTURES AS-BUILT IF ON-SITE. CONSULTING STRUCTURAL AND MECHANICAL PRIOR TO COMMENCEMENT OF WORK AND BEFORE ANY DISCREPANCIES TO MEMAR. DESIGN DRAWINGS & SPECIFICATIONS ARE ALL PROPERTY OF MEMAR UNDER COPY RIGHT ACT AND MUST NOT BE USED FOR ANY OTHER PROJECT AND/OR BY ANY OTHER PERSON WITHOUT ORIGINAL CLIENT WITHOUT WRITTEN PERMISSION.

DATE	ISSUED FOR:
FEB 27-2018	FOR IDING REVIEW APPLICATION
MAR 30-2018	FOR COA APPLICATION

DRAWING TITLE:  
**E-04 SOUTH\_FRONT ELEV**

PROJECT TITLE/ADDRESS:  
**41 ELGIN ST, MARKHAM**

DRAWN BY  
D.N.

CHECKED BY  
S.T.

SCALE:  
1:100

LAST MODIFIED ON:  
Wednesday, April 4, 2018



"Memor Architects Inc."  
2323 Yonge St, Unit 503  
Toronto, ON, M4P 2C9  
T: 416-575-4448



**A.10**



ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY IN NATURE AND APPROVED BY THE CITY AND SHOULD NOT BE USED FOR ANY CONTRACT OR FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN PERMISSION OF MEMAR ARCHITECTS INC. ANY CHANGES TO THE DRAWINGS OR DOCUMENTS MUST BE MADE IN WRITING AND APPROVED BY MEMAR ARCHITECTS INC. BEFORE ANY CONSTRUCTION BEGINS. MEMAR ARCHITECTS INC. IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS IN THIS DRAWING OR DOCUMENT. MEMAR ARCHITECTS INC. IS NOT RESPONSIBLE FOR ANY CONSTRUCTION DEFECTS OR DAMAGES TO ANY PROPERTY OR PERSONS. MEMAR ARCHITECTS INC. IS NOT RESPONSIBLE FOR ANY COSTS INCURRED BY ANY OTHER PERSON OR ENTITY IN CONNECTION WITH THIS DRAWING OR DOCUMENT.

DATE	ISSUED FOR:
FEB 27-2018	FOR ZONING REVIEW APPLICATION
MAR 30-2018	FOR COA APPLICATION

DRAWING TITLE: <b>E-03 NORTH_REAR ELEV</b>
PROJECT TITLE/ADDRESS: <b>41 ELGIN ST, MARKHAM</b>

DRAWN BY: D.N.
CHECKED BY: S.T.


SCALE: 1:100
LAST MODIFIED ON: Wednesday, April 4, 2018




"Memar Architects Inc."  
2323 Yonge St, Unit 503  
Toronto, ON, M4P 2C9  
T: 416-575-4448



**A.11**



<small>ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY UNLESS APPROVED BY THE CITY AND MUST NOT BE USED FOR ANY CONSTRUCTION BEFORE GRANTS OF PERMITS. PERMIT CONTRACTORS/TRADESMEN MUST VERIFY ALL DIMENSIONS/NOTES/DETAILS AS SHOWN FOR INFORMATION INCLUDING STRUCTURAL AND MECHANICAL PRIOR TO COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO MEMAR. DESIGN DRAWINGS &amp; SPECIFICATIONS ARE THE PROPERTY OF MEMAR. REPRODUCE OR COPY THIS DRAWING FOR ANY OTHER PROJECT AND/OR BY ANY OTHER PERSON WITHOUT WRITTEN PERMISSION.</small>	DATE	ISSUED FOR:	DRAWING TITLE:	DRAWN BY	SCALE:		"Memor Architects Inc." 2323 Yonge St, Unit 503 Toronto, ON, M4P 2C9 T: 416-575-4448		<b>A.12</b>
	FEB 27-2018	FOR ZONING REVIEW APPLICATION	<b>E-05 WEST ELEV</b>	D.N.	1:125				
	MAR 30-2018	FOR COA APPLICATION	PROJECT TITLE/ADDRESS:	CHKD BY	LAST MODIFIED ON:				
			<b>41 ELGIN ST, MARKHAM</b>	S.T.	Wednesday, April 4, 2018				



ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY UNLESS APPROVED BY THE CITY AND MUST NOT BE USED FOR ANY CONSTRUCTION BEFORE OBTAINING THE NECESSARY PERMITS FROM THE CITY OF MARKHAM. CONTRACTORS MUST VERIFY ALL DIMENSIONS AND CONDITIONS AS SHOWN ON DRAWINGS INCLUDING STRUCTURAL AND MECHANICAL PRIOR TO COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO MEMAR.

MEMAR ARCHITECTS & SPECIFICATIONS ARE ALL PROPERTY OF MEMAR UNDER COPYRIGHT AND MUST NOT BE USED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION OF MEMAR.

DATE	ISSUED FOR:
FEB 23-2018	FOR ZONING REVIEW APPLICATION
MAR 30-2018	FOR COA APPLICATION

<b>DRAWING TITLE:</b>	<b>E-06 EAST ELEV</b>
<b>PROJECT TITLE/ADDRESS:</b>	<b>41 ELGIN ST, MARKHAM</b>

<b>DRAWN BY:</b>	D.N.
<b>CHECKED BY:</b>	S.T.

<b>SCALE:</b>	1:125
<b>LAST MODIFIED ON:</b>	Wednesday, April 4, 2018

**MEMAR ARCHITECTS**

"Memar Architects Inc."  
2323 Yonge St, Unit 503  
Toronto, ON, M4P 2C9  
T: 416-575-4448



**A.13**